BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Project Division
B.B.M.P., Bangalore - 92

MODIFIED APPROVED SCHEDULE - B

Name of Work: INCREASING THE IMPOUNDING CAPACITY OF ALLASANDRA LAKE AND ALLIED WORKS

Sl. No.	App Qty	Description	Unit	Rates Quoted by M/s.Parchitha Constructions	
				In Figures	In Words
1	540.68	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	130.00	One Hundred Thirty Rupees and Zero Paise
2	130.58	Providing and laying in position plain cement concrete of mix M10 with OPC Cement @220kgswith 20mm and down size graded granite metal coarse aggregates @0.84 cum and fine aggregates @0.56cum,machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	3800.00	Three Thousand Eight Hundred Rupees and Zero Paise
3	189.53	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-320 Kg/cum) ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	4400.00	Four Thousand Four Hundred Rupees and Zero Paise

For Parichitha Constructions

Signature of the Contractor

Executive Engineer (Project)

Sl. No.	App Qty	Description	Unit	Rates Quoted by M/s.Parchitha Constructions	
				In Figures	In Words
4	84.00	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-25 (1:1:2) (Cement-340 Kg/cum) ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	4900.00	Four Thousand Nine Hundred Rupees and Zero Paise
5	11.00	Providing & fabricating TMT steel reinforcement for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	mt	59000.00	Fifty Nine Thousand Rupees and Zero Paise
6	1020.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	180.00	One Hundred Eighty Rupees and Zero Paise
7	162.20	Filling available excavated earth in sides of foundations in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering including cost of all labour complete as per specifcations. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	90.00	Ninety Rupees and Zero Paise
8	54000.00	Earthwork excavation for foundation in all kinds of soil including boulders up to 0.60m dia (0.113cum) for dam barage, spilway,intake surface and other appurtennant works and placing the excavted soil nearly in dump area or disposing off the same as per directions of Engineer in charge and lead of 8km for conveying and breaking of clods complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	111.00	One Hundred Eleven Rupees and Zero Paise
9	0.72	Clearing grass and removal of rubbish by manual means and stacking outside the periphery of the area cleaned complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	11000.00	Eleven Thousand Rupees and Zero Paise

For Parichitha Constructions

Signature of the Contractor

Proprietor

Executive Engineer (Project

Sl. No.	App Qty	Description	Unit	Rates Quoted by M/s.Parchitha Constructions	
				In Figures	In Words
10	43.88	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. --- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	2600.00	Two Thousand Six Hundred Rupees and Zero Paise
11	41.51	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:8, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	2800.00	Two Thousand Eight Hundred Rupees and Zero Paise
12	90.00	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	65.00	Sixty Five Rupees and Zero Paise
13	90.00	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer- in - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Rmt	780.00	Seven Hundred Eighty Rupees and Zero Paise
14	90.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Rmt	250.00	Two Hundred Fifty Rupees and Zero Paise

For Parichitha Constructions

Proprietor

Signature of the Contractor

Executive Engineer (Project

Sl. No.	App Qty	Description	Unit	Rates Quoted by M/s.Parchitha Constructions	
				In Figures	In Words
15	800.00	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	450.00	Four Hundred Fifty Rupees and Zero Paise
16	1625.28	Providing and laying heavy duty cobble stones 65mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	610.00	Six Hundred Ten Rupees and Zero Paise
17	360.00	Providing Ceramic tiles of approved make,shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment , including cost of materials, labour, curing, complete as per specifications._do_ for Ceramic Tiles of size 30x30cms ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	750.00	Seven Hundred Fifty Rupees and Zero Paise
18	2000.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450x200x400mm ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	No	220.00	Two Hundred Twenty Rupees and Zero Paise
19	1183.70	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specificatins. Specification No.KRBS 800.3 MORT & H Specification No.800 ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	39.00	Thirty Nine Rupees and Zero Paise
20	1183.70	Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications. MORTH Specification No. 803 24.8.1 Painting on Steel Surface. ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	40.00	Forty Rupees and Zero Paise

For Parichitha Constructions

Signature of the Contractor

Executive Engineer (Project

Sl. No.	App Qty	Description	Unit	Rates Quoted by M/s.Parchitha Constructions	
				In Figures	In Words
		EIRL			
1	2620.80	KSRRB M300-Construction of Embankment with Material Gravel/Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications, (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	195.58	One Hundred Ninety Five Rupees and Fifty Eight Paise
2	391.50	KSRRB M2500-4.1. Providing and laying Pitching on slopes laid over prepared filter media including boulder apron laid dry in front of toe of embankment complete as per drawing and Technical specifications A. Stone / Boulder ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Cum	1091.02	One Thousand Ninety One Rupees and Two Paise
3	154.90	Manufacturing, supplying & fixing on position MS Grill made out of MS Flats 25x6mm size and center for intermediates verticles of size 40x60mm at 12 cms, c/c 15cms center to center with necessary rings and flowers, rings of 50cms and 25mm dia size made out of 25x6mm MS Flats, Horizontal MS Flats of size 40mmx8mm at bottom with necessary lower supporters of MS Angle of 50x50x6mm of stand & fixing in concrete as per the Grill design drawing and including cutting, bending to shape, welding, grinding etc., complete and all the steel surface shall be applying red lead mix primer coat free from dust and painted with two coats of approved enamel metallic painting. The work includes fixing the MS Grills in position with cement concrete (1:2:4) (Excluding the cost of concrete) with cutting the grooves in the existing concrete surface including cost of all materials, cost of labour charges, an equipment and all other incidental charges for successful compaction of the work ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Sqm	4338.00	Four Thousand Three Hundred Thirty Eight Rupees and Zero Paise
4	50.00	Providing and laying reinforced cement concrete pipe NP2 for culverts including pointing ends, and fixing collars with cement mortar 1:2 including cost of all materials, labour, curing complete as per specifications. Specifications. No. KSRB 1000, 2300 MOST Specification No.1000 / 2300 -do- 600mm dia ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Mtr	2170.53	Two Thousand One Hundred Seventy Rupees and Fifty Three Paise

For Parichitha Constructions

Signature of the Contractor

Proprietor

Executive Engineer (Project

Sl. No.	App Qty	Description	Unit	Rates Quoted by M/s.Parchitha Constructions	
				In Figures	In Words
5	10214.80	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications ---- With all lead and lift and work to be executed as per Directions of Engineer-in-charge	Mtr	72.86	Seventy Two Rupees and Eighty Six Paise

I am prepare to execute work at the rates written by me in Schedule "B".

For Parichitha Constructions

Signature of the Contractor

Proprietor

Executive Engineer
Project Division
Yelahanka Zone, BBMP

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Bangalore 92

For Parichitha Constructions

Signature of the Contractor

Proprietor

Executive Engineer (Project)